

Addendum #2, posted 9/1/17

RFP#17-040-30 – Fairground Building Roof Replacements

Addendum #2 is a redaction of Addendum #1. The original language in the first addendum should not have been listed as change for the Swine and Sheep Barn; the change is for the Baby Animal and Show Barn. No changes are made for the Swine and Sheep Barn.

- **BABY ANIMAL AND SHOW BARN**

- Roofing Replacement
  - Remove and dispose of existing ridge cap and rake trim
  - Remove and dispose of existing roof steel
  - Move all peak purlins down to accommodate ridgelite
  - Replace approximately 12 existing damaged purlins
  - Install 29 gauge McElroy MaxRib 100 with SMP coating. Evergreen in color.
  - Moisturelok applied to roof steel
  - ~~▪ Install 23" Fiberglass Ridgelite with vented closures.~~
  - Install all flashing and trim for a complete roof system.
- Original Language:
  - ~~▪ Install 23" Fiberglass Ridgelite with vented closures~~
- New Language:
  - Install Polycarbonate Ridgelite with vented closure